



Real People. Real Solutions.

2022 Street & Utility Improvements Project Update

October 24, 2022

Construction schedule:

Start: May 2022 Finish: October 2022 Final Paving: Summer 2023

Contacts:

Bolton & Menk, Inc.

1960 Premier Drive Mankato, MN 56001 Phone: 507-625-4171 Fax: 507-625-4177 www.bolton-menk.com

Jeffrey Domras, P.E.

(Mapleton Consultant City Engineer)

Cell: 507-381-0857

 $\hbox{E-mail:} \ \underline{\hbox{Jeffrey.Domras@bolton-menk.com}}$

Patrick Schroepfer

(Construction Representative)

Cell: 507-327-5318

E-mail: Patrick.Schroepfer@bolton-menk.com

City of Mapleton

104 2nd Ave NE Mapleton, MN 56065 Amber Duncanson (City Clerk) Office: 507-524-3492

Office. 507-524-5492

a.duncanson@mapletonmn.gov

Hunter Chaffee (Public Works Supervisor) Cell: 507-520-0373

publicworks@mapletonmn.gov

Holtmeier Construction, Inc.

Jim Voda (Project Manager) 3301 3rd Avenue Mankato, MN 56001 Office: 507-389-9112 jvoda@holtmeierinc.com



Turf Maintenance

The contractor has started the sod installation on disturbed boulevard areas related to the 2022 Construction Project. Below is a list of best practices for sod establishment and maintenance.

• Fall of 2022 Best Practices:

- The contractor will water the sod to full saturation immediately after placement.
- The sod may need to be watered again 7-10 days after placement. This second watering is not needed if the sod receives 1" of rain, snow cover, or if temps drop below 32° F.
- Avoid mowing the newly placed sod this fall.
- Use care when raking leaves on the newly placed sod.

Spring of 2023 Best Practices:

- After snow melt and once the soil temperatures have reached
 40°F the contractor will apply water to the sod if required.
- When the sod reaches a uniform height of 6" tall, mow it to 4" high. Repeat this process a second and third time. The sod can now be mowed with the rest of the lawn.
- Avoid mowing newly established sod when conditions are hot (85° F) and dry.
- Control weeds by hand pulling

